

City of Oakley

ADDENDUM NO. 3 to contract documents for

CIP 250 – Laurel Road Resurfacing Project (Empire Ave. to O’Hara Ave.)

BID OPENING DATE: June 29, 2021 2:00 PM

Notice is hereby given that the following clarifications and revisions are made to the above referenced contract documents:

Updates to the Specifications:

Bidders shall clearly tab or identify the following locations in the Bid Proposal:

- Bid Summary Totals
- All Bid Addendums
- Bidder’s Bond

PART I - Bid Schedule

Updated Bid Schedule to be used for the bid (attached)

PART III – Technical Specifications

1-1.17 HOT MIX ASPHALT (HMA)

GENERAL

Do not leave a vertical joint more than 0.15 foot high between adjacent lanes open to public traffic. Place W8-17 signs adjacent to the traveled way’s outside edge. Place the first W8-17 sign where the vertical joint begins in the direction of travel on that lane. Place the W8-17 signs at 1,000 foot maximum intervals and at ramps and public roads entering the traffic lane.

MEASUREMENT AND PAYMENT

The contract price paid per ton for “Hot Mix Asphalt Overlay (3.5 Inches)” shall include full compensation for furnishing all labor, materials, temporary tapers, tools, equipment, and incidentals, and for doing all the work involved in HMA, complete in place, including surface preparation, tack coat, preparation, submission and verification testing costs for the JMF; providing the Contractor’s Quality Control Plan; and the costs of coring to verify core densities if required, as shown on the plans, as specified in the Standard Specification and these special provisions, and as directed by the Engineer. Contractor shall provide certification of compliance and delivery manifest when asphalt is placed.

The contract price paid per ton for "Hot Mix Asphalt Overlay (6 Inches)" in Bid Alternate 1 shall include full compensation for furnishing all labor, materials, temporary tapers, tools, equipment, and incidentals, and for doing all the work involved in HMA, complete in place, including surface preparation, tack coat, preparation, submission and verification testing costs for the JMF; providing the Contractor's Quality Control Plan; and the costs of coring to verify core densities if required, as shown on the plans, as specified in the Standard Specification and these special provisions, and as directed by the Engineer. Contractor shall provide certification of compliance and delivery manifest when asphalt is placed.


The contract price paid per ton for "Hot Mix Asphalt Overlay (4.5 Inches)" in Bid Alternate 2 shall include full compensation for furnishing all labor, materials, temporary tapers, tools, equipment, and incidentals, and for doing all the work involved in HMA, complete in place, including surface preparation, tack coat, preparation, submission and verification testing costs for the JMF; providing the Contractor's Quality Control Plan; and the costs of coring to verify core densities if required, as shown on the plans, as specified in the Standard Specification and these special provisions, and as directed by the Engineer. Contractor shall provide certification of compliance and delivery manifest when asphalt is placed.

1-1.18 RUBBERIZED HOT-MIX ASPHALT

MEASUREMENT AND PAYMENT

The contract price paid per ton for "Rubberized Hot Mix Asphalt Overlay (2.5-inches)" shall include full compensation for furnishing all labor, materials, temporary tapers, tools, equipment, and incidentals and doing all work involved in constructing asphalt concrete, including mix design preparation, contractor quality control according to Section 39, "Hot Mix Asphalt," of the Standard Specifications, quality control plan and quality control testing and reporting, complete in place, as shown on the plans and as specified in the Standard Specifications and these Special Provisions or as directed by the Engineer.

All bidders shall acknowledge receipt and acceptance of Addendum No. 3 by signing in the space provided at the end of this Addendum and submitting the signed addendum with their proposal.



Jason Kabalin
Capital Projects Engineer
June 25, 2021

Contractor Signature

Date

Company Name

A. UNIT PRICE SCHEDULE

The undersigned, Pursuant to and in compliance with your Notice to Contractors and the Contract Documents relating to the **FY 2020-2021 LAUREL RD RESURFACING PROJECT (EMPIRE AVE TO O'HARA AVE), CIP NO. 250**, including Addenda No. _____, _____, _____, as Bidder, declares that the only persons or parties interested in this proposal as principals are those named herein; that this proposal is made without collusion with any other person, firm, or corporation; that he has carefully examined the location of the proposed work, the annexed proposed form of contract, and the plans therein referred to; and he proposes and agrees if this proposal is accepted that he will contract with the City of Oakley in the form of the scope of the contract annexed hereto, to provide all necessary machinery, tools, apparatus, and other means of construction, and to do all the work and furnish all the materials specified in the contract, in the manner and time therein prescribed, and according to the requirements of the Engineer as therein set forth, and that he will take in full payment therefore the following item prices, to wit:

BASE BID SCHEDULE

ITEM NO.	BID ITEMS	PAY REF	UNIT	TOTAL QTY	UNIT PRICE	TOTAL COST
1	Mobilization	10-1.02	LS	1		
2	Traffic Control and Construction Area Signs	10-1.03	LS	1		
3	Water Pollution Control Plan	10-1.04	LS	1		
4	Tree Protection	10-1.06	LS	1		
5	Adjust Sanitary Sewer Manhole Ring and Cover to Grade	10-1.08	EA	5		
6	Adjust Storm Drain Manhole Ring and Cover to Grade	10-1.08	EA	13		
7	Adjust Water Valve Box and Cover to Grade	10-1.08	EA	46		
8	Adjust Survey Monument Box and Cover to Grade	10-1.08	EA	5		
9	Remove Concrete Curb and Gutter	10-1.09	LF	207		
10	Concrete Curb and Gutter	10-1.09	LF	207		
11	Repair Sidewalk	10-1.11	SF	98		
12	Retrofit Curb Ramp Detectable Warning Surface	10-1.10	EA	2		
13	Remove Traffic Striping, Markings and Markers & Prepare Lead Compliance Plan	10-1.12	LS	1		
14	Cold Plane AC Pavement (5 In – 6 In Depth)	10-1.13	SY	45,297		
15	Subgrade Preparation	10-1.14	SY	45,297		
16	Subgrade Over-Excavation (Revocable Item)	10-1.15	SY	3,171		
17	Hot Mix Asphalt Overlay (3.5 Inches)	10-1.17	TON	9,810		
18	Rubberized Hot Mix Asphalt (2.5 Inches)	10-1.18	TON	7,007		
19	Thermoplastic Traffic Striping - Caltrans Detail 9	10-1.20	LF	9,302		
20	Thermoplastic Traffic Striping - Caltrans Detail 21	10-1.20	LF	5		
21	Thermoplastic Traffic Striping - Caltrans Detail 22	10-1.20	LF	18		

ITEM NO.	BID ITEMS	PAY REF	UNIT	TOTAL QTY	UNIT PRICE	TOTAL COST
22	Thermoplastic Traffic Striping - Caltrans Detail 24	10-1.20	LF	186		
23	Thermoplastic Traffic Striping - Caltrans Detail 25A	10-1.20	LF	290		
24	Thermoplastic Traffic Striping - Caltrans Detail 25B	10-1.20	LF	283		
25	Thermoplastic Traffic Striping - Caltrans Detail 29	10-1.20	LF	24		
26	Thermoplastic Traffic Striping - Caltrans Detail 38	10-1.20	LF	2,381		
27	Thermoplastic Traffic Striping - Caltrans Detail 38A	10-1.20	LF	260		
28	Thermoplastic Traffic Striping - Caltrans Detail 39	10-1.20	LF	1,735		
29	Thermoplastic Traffic Striping - Caltrans Detail 39A	10-1.20	LF	18		
30	Thermoplastic 6" White Line	10-1.20	LF	678		
31	Thermoplastic Limit Line (White)	10-1.20	LF	405		
32	Thermoplastic 12" Basic Crosswalk (White or Yellow)	10-1.20	LF	2,794		
33	Thermoplastic Bike Lane Buffer	10-1.20	LF	7,452		
34	Green MMA Pavement Marking	10-1.20	SF	6,004		
35	Bike Buffer Rumble Strip	10-1.21	EA	5,960		
36	Thermoplastic Pavement Markings	10-1.20	SF	1,447		
37	Channelizer	10-1.22	EA	56		
38	Salvage and Reset Sign and/or Signpost	10-1.23	EA	2		
39	Install R26 Signs	10-1.24	EA	8		
40	Blank Out 'No Right Turn On Red' LED Sign	10-1.25	EA	1		
41	SW24-1 and SW24-3 Signs	10-1.26	EA	2		

Total Base Bid (Items 1-41) \$ _____ **(Numbers)**

_____ **Dollars (Written)**

ALTERNATE BID NO. 1 - BID SCHEDULE

ITEM NO.	BID ITEMS	PAY REF	UNIT	TOTAL QTY	UNIT PRICE	TOTAL COST
A1-1	Cold Plane AC Pavement (5 In – 6 In Depth)	10-1.13	SY	45,297		
A1-2	Subgrade Preparation	10-1.14	SY	45,297		
A1-3	Subgrade Over-Excavation (Revocable Item)	10-1.15	SY	3,171		
A1-4	Fiber Reinforced HMA Overlay (3.5 Inches)	10-1.19	TON	9,810		
A1-5	Rubberized Hot Mix Asphalt (2.5 inches)	10.1.18	TON	7,007		

Total Alternate Bid No. 1 Bid (Items A1-1 through A1-5) \$ _____
(Numbers)

Dollars (Written)

ALTERNATE BID NO. 2 - SCHEDULE

ITEM NO.	BID ITEMS	PAY REF	UNIT	TOTAL QTY	UNIT PRICE	TOTAL COST
A2-1	Cold Plane AC Pavement (5 In – 6 In Depth)	10-1.13	SY	45,297		
A2-2	Subgrade Preparation	10-1.14	SY	45,297		
A2-3	Subgrade Over-Excavation (Revocable Item)	10-1.15	SY	3,171		
A2-4	Hot Mix Asphalt Overlay (6 inches)	10-1.17	TON	16,817		

Total Alternate No. 2 Bid (Items A2-1 through A2-4) \$ _____
(Numbers)

Dollars (Written)

ALTERNATE BID NO. 3 - SCHEDULE

ITEM NO.	BID ITEMS	PAY REF	UNIT	TOTAL QTY	UNIT PRICE	TOTAL COST
A3-1	Cold Plane AC Pavement (6 In – 7 In Depth)	10-1.13	SY	45,297		
A3-2	Subgrade Preparation	10-1.14	SY	45,297		
A3-3	Subgrade Over-Excavation (Revocable Item)	10-1.15	SY	3,171		
A3-4	Hot Mix Asphalt Overlay (4.5 inches)	10-1.17	TON	12,613		
A3-5	Rubberized Hot Mix Asphalt (2.5 inches)	10-1.18	TON	7,007		

Total Alternate No. 3 Bid (Items A3-1 through A3-5) \$ _____
 (Numbers)

 Dollars (Written)

BID SUMMARY

BIDDER: _____

BID SUMMARY	
BASE BID	TOTAL PRICE IN FIGURES \$ TOTAL PRICE IN WORDS
BID ALTERNATE NO. 1	TOTAL PRICE IN FIGURES \$ TOTAL PRICE IN WORDS
BID ALTERNATE NO. 2	TOTAL PRICE IN FIGURES \$ TOTAL PRICE IN WORDS
BID ALTERNATE NO. 3	TOTAL PRICE IN FIGURES \$ TOTAL PRICE IN WORDS

The basis of award for this project is the Base Bid. The City reserves the right to add any combination of Bid Alternates to the project at its own discretion.

City shall have the right to remove Base Bid Items 14, 15, 16, 17, and 18, and include Bid Alternate No. A-1 through item A1-5 (if awarded) from the contract scope of work. City shall also have the right to remove Base Bid Items 14, 15, 16, 17, and 18, and include Bid Alternate No. 2 items A2-1 through A2-4. City shall also have the right to remove Bid Items 14, 15, 16, 17, and 18, and include Bid Alternate No. 3 item A3-1 through A3-5. City's contractor shall not be entitled to any additional time extension or compensation, including overhead or profit, in the event Base Bid Items 14,15,16,17, and 18 are removed from the project scope. City shall notify City's contractor if it will be removing any of the items from the scope of work within ten (10) working days after the Notice of Award.