

City of Oakley
ADDENDUM NO. 3 to contract documents for
CIP 246 – FY 2020/21 Street Repair and Resurfacing Project

BID OPENING DATE: May 26, 2022 2:00 PM

Notice is hereby given that the following clarifications and revisions are made to the above referenced contract documents:

Updates to the Bid Documents:

Supplemental Information

Bid Item Quantities by Streets

All bidders shall acknowledge receipt and acceptance of Addendum No. 1 by signing in the space provided at the end of this Addendum and submitting the signed addendum with their proposal.



Jason Kabalin
Capital Projects Engineer
May 24, 2022

Contractor Signature

Date

Company Name

CITY OF OAKLEY
2020/2021 STREET REPAIR & RESURFACING PROJECT - CIP #246
BID ITEM QUANTITIES

BID ITEM NO.	BID ITEM	PAYMENT REFERENCE	UNIT	Full Depth HMA 6"	Slurry Seal w/DO's	Full Depth HMA 6"	Full Depth HMA 4"	Full Depth HMA 4"	Full Depth HMA 4"	Full Depth HMA 4"	Full Depth HMA 4"	Slurry & ARAM
				Live Oak Avenue	Live Oak Avenue	Live Oak Avenue	Fontes Way	Miguel Drive	Pecan Lane	Rua Pera	Teixeira Way	Brownstone Road
				Oakley Road to Sutter Street	Sutter Street to Knox Lane	Knox Lane to Neroly Road	Teixeira Way to Miguel Drive	Main Street to Teixeira Way	Teixeira Way to 1601 Pecan Way	Miguel Drive to End	Miguel Drive to End	O'Hara Avenue to Main Street
				70,057	80,827	13,197	9,558	45,148	4,528	3,482	29,874	130,919
1	Mobilization, Bonds & Insurance	10-1.02	LS									
2	Traffic Control & Construction Area Signs	10-1.03	LS									
3	Water Pollution Control Program	10-1.04	LS									
4	Potholing	10-1.06	LS									
5	Crack Seal & Slurry Seal (Type II w/Black Rock)	10-1.16	SF		80,827							86,003
6	ARAM Cape Seal	10-1.15	SF									44,916
7	3/8" HMA (Type A) PG 64-10	10-1.09	TN									154
8	1/2" HMA (Type A) PG 64-10	10-1.09	TN	2,944		550	255	1,204	121	93	797	
9	Miscellaneous Paving Transition	10-1.09	SF	6,615		1,048						
10	Construct / Remove & Replace HMA Dike	10-1.09	LF	388		67						
11	Remove & Replace 5" HMA	10-1.11	SF		16,400							
12	Remove & Replace 6" HMA	10-1.11	SF									24,925
13	6" Deep Lift Stabilization (Allowance)	10-1.11	SF	3,503	820	660	478	2,257	226	174	1,494	
14	Prune & Remove Tree Roots (Under HMA Repairs)	10-1.08	EA									5
15	Cold Plane 4"	10-1.12	SF				9,558	45,148	4,528	3,482	29,874	
16	Cold Plane 6"	10-1.12	SF	59,600		12,020						
17	Grind AC Flush with Gutter Lip	10-1.12	LF		80							
18	Off Haul & Dispose Sierracrete (Allowance)	10-1.12	CY				23	111	11	9	73	
19	Roadway Excavation	10-1.13	CY	585								
20	Roadway Infill	10-1.13	CY			25						
21	Roadway Grading	10-1.14	SF	70,057		13,197						
22	Retention Basin Grading	10-1.14	SF	854								
23	Hydroseeding	10-1.23	SF	854								
24	Lower Storm Drain Manhole Cover	10-1.20	EA		1			6			3	
25	Lower Sanitary Sewer Manhole Cover	10-1.20	EA	1	2							
26	Lower Survey Monument Cover	10-1.20	EA	1	1			8			3	
27	Lower Water Valve Cover	10-1.20	EA	6		2		8			8	
28	Adjust Storm Drain Manhole Cover to Finish Grade	10-1.20	EA		5			6			3	
29	Adjust Sanitary Sewer Manhole Cover to Finish Grade	10-1.20	EA	1	5							
30	Adjust Survey Monument Cover to Finish Grade	10-1.20	EA	1	1			8			3	
31	Adjust Water Valve Cover to Finish Grade	10-1.20	EA	6		2		8			8	
32	Install Blue RPM at Fire Hydrant	10-1.21	EA	3	4	1						2
33	12" White Crosswalk/Limit Line (Thermo)	10-1.21	LF	60		205	38	85	28	19		114
34	Stripping Detail #22 (Thermo & Markers)	10-1.21	LF	2,669	1,915	505	100	669	50	50	26	5,047
35	Stripping Detail #27B (Thermo & Markers)	10-1.21	LF	5,442	1,719	1,032						7,285
36	Stripping Detail #27C (Thermo)	10-1.21	LF		72							
37	Stripping Detail #38 (Thermo & Markers)	10-1.21	LF		240							140
38	Stripping Detail #39 (Thermo)	10-1.21	LF									2,304
39	Stripping Detail #39A (Thermo)	10-1.21	LF									100
40	Type I (10'-0") Arrow (Thermo)	10-1.21	EA		9							2

CITY OF OAKLEY
 2020/2021 STREET REPAIR & RESURFACING PROJECT - CIP #246
 BID ITEM QUANTITIES

BID ITEM NO.	BID ITEM	PAYMENT REFERENCE	UNIT	Full Depth HMA 6"	Slurry Seal w/DO's	Full Depth HMA 6"	Full Depth HMA 4"	Full Depth HMA 4"	Full Depth HMA 4"	Full Depth HMA 4"	Full Depth HMA 4"	Slurry & ARAM
				Live Oak Avenue	Live Oak Avenue	Live Oak Avenue	Fontes Way	Miguel Drive	Pecan Lane	Rua Pera	Teixeira Way	Brownstone Road
				Oakley Road to Sutter Street 70,057	Sutter Street to Knox Lane 80,827	Knox Lane to Neroly Road 13,197	Teixeira Way to Miguel Drive 9,558	Main Street to Teixeira Way 45,148	Teixeira Way to 1601 Pecan Way 4,528	Miguel Drive to End 3,482	Miguel Drive to End 29,874	O'Hara Avenue to Main Street 130,919
41	Type IV (L or R) Arrow (Thermo)	10-1.21	EA		3							4
42	Type VII (R) Arrow (Thermo)	10-1.21	EA									2
43	Bike Lane Symbol w/Person (Thermo)	10-1.21	EA									10
44	Bike Lane Arrow (Thermo)	10-1.21	EA									10
45	Pavement Marking "AHEAD" Legend (Thermo)	10-1.21	EA									4
46	Pavement Marking "STOP" Legend (Thermo)	10-1.21	EA	2		3	2	2	1	1		10
47	Aerial Marker (Paint)	10-1.21	EA		1							
48	Shoulder Backing	10-1.19	LF	3,189		686						6,553
49	Relocate Roadside Sign & Post	10-1.22	EA	2								
50	Install Roadside Sign & Post	10-1.22	EA	1								
51	Relocate Mailbox	10-1.22	EA	2								